Measured Damage and Retained Areas

Visit Details

Claim: CLM-26-402550. Property: Cedarline Medical Center LLC, 1454 Alder Court, Suite D.

Inspection completed 2026-08-27 by Elliot Chen.

The medical center comprises two connected wings and an enclosed transfer corridor. The contractor's drawing colors both wings as one work zone. Inspection access was available to the north wing and the corridor, and staff escorted the survey team through the south wing while clinics continued. Separate sketches record the inspected boundaries.

Interior Scope

North-wing consulting rooms have saturated wall bases and detached sheet-floor seams. The transfer corridor has ceiling staining below the open riser and buckled floor sections at its low point. South-wing rooms have intact floor adhesion and dry wall cores at the inspection openings. The contractor's proposal includes full replacement through the south wing as well as the north.

Electrical Scope

Water reached the north-wing low-level outlets and the corridor junction box. Test readings for those circuits were below the electrical contractor's release criterion. The south-wing distribution board stayed energized on a separate feed; sampled devices there were clean and passed the site test. Circuit identifiers are recorded beside each opening.

Demolition Scope

Marked demolition includes north-wing lower partitions, wet corridor ceiling bays, and the flooring inside the measured wet perimeter. The rear stair enclosure was used for a dry comparison and is not marked on the removal sketch. The submitted waste schedule assumes removal from both wings; the inspection sketch shows retained south-wing assemblies.

Millwork Scope

Five north-wing counter bases have swollen substrates. Their countertops can be lifted and reset. South-wing examination storage has square carcasses, level doors and dry rear surfaces. The proposal contains complete runs for both wings. The survey drawing identifies individual wet cabinet bases rather than every cabinet at the property.

Prior Conditions

The riser access opening exposes clean pipe clamps and firm studs above the fresh wet boundary. No prior staining is visible behind the removable corridor panels. The facilities log records an intact header at the previous pressure-gauge replacement.

Microbial Observations

Accessible cavities were checked under task lighting. No visible colonies were recorded in the wet north-wing openings or in the south-wing comparison openings.

Room Observation Register

Comparative meter readings are unitless indices on a 0-100 scale, not moisture percentages. Each room spot is compared with an adjacent retained substrate on the same instrument setting. Readings describe the visit condition and do not date the wetting.

Measured Damage and Retained Areas

Point / location	Assembly / record	Observation / method	Boundary / reference
1A - North consulting wing	Lower gypsum and sheet floor	saturated and detached	Removal boundary marked red
1B - North consulting wing	Inspection method	Lifted-edge adhesion comparison	Field visit 2026-08-27; sample point 1
1C - North consulting wing	Lower substrate spot reading	73 on relative 0-100 scale	Accessible surface beside lower gypsum and sheet floor
1D - North consulting wing	Retained comparison point	12 on same instrument scale	Removal boundary marked red
2A - Transfer corridor	Ceiling grid and floor low point	water staining and buckled seams	High end remains dry
2B - Transfer corridor	Inspection method	Lifted-edge adhesion comparison	Field visit 2026-08-27; sample point 2
2C - Transfer corridor	Lower substrate spot reading	52 on relative 0-100 scale	Accessible surface beside ceiling grid and floor low point
2D - Transfer corridor	Retained comparison point	14 on same instrument scale	High end remains dry
3A - South consulting wing	Wall-core control openings	dry gypsum and firm adhesive	Openings resealed after inspection
3B - South consulting wing	Inspection method	Visual survey of exposed surfaces and access opening	Field visit 2026-08-27; sample point 3
3C - South consulting wing	Lower substrate spot reading	10 on relative 0-100 scale	Accessible surface beside wall-core control openings
3D - South consulting wing	Retained comparison point	10 on same instrument scale	Openings resealed after inspection
4A - South examination storage	Counter bases	square doors and dry rear faces	No removal marks on sketch
4B - South examination storage	Inspection method	Visual survey of exposed surfaces and access opening	Field visit 2026-08-27; sample point 4
4C - South examination storage	Lower substrate spot reading	11 on relative 0-100 scale	Accessible surface beside counter bases
4D - South examination storage	Retained comparison point	12 on same instrument scale	No removal marks on sketch

Inspection Record

Working notes were entered during the 2026-08-27 visit. Room labels in the table follow the site route used by Elliot Chen; they are not contractor estimate line numbers.

The table records inspected positions and comparison areas. It is not a full quantity takeoff or an invoice. Closed assemblies are distinguished from opened observations in the narrative.