Service Chase Access Study

Visit Details

Claim: CLM-26-902082. Property: Harborview Diagnostics LLC, 1471 Alder Court, Suite E.

Inspection completed 2026-08-21 by Naomi Brooks.

A concealed vertical chase divides the diagnostic rooms from the staff passage. There is no removable hatch at the failed connection. The survey included the visible wet finishes and the route from the passage to the connection; these are drawn in different hatch patterns on the field sketch.

Prior Conditions

The passage finish layers are sound away from the camera hole. The exposed metal framing is clean. The observed moisture boundary begins on the diagnostic-room side of the chase and stops before the dry access strip.

Interior Scope

Water spread across the diagnostic-room floor and softened the adjacent partition bases. In the staff passage, a painted ceiling strip between the dry door head and the chase must be opened to create a tool path. The finish strip is dry on both faces at the test holes. Reinstatement will restore the original passage enclosure after plumbing access.

Millwork Scope

The diagnostic counter base has swollen ends. Its solid surface top is intact. A fixed return panel in the staff passage must be detached and reinstated to admit the plumbing tools; it has no water deformation at the inspection date.

Demolition Scope

Wet gypsum and loose floor finishes are marked D on the sketch. The dry passage ceiling and return panel are marked A, identifying the physical route needed to reach the connection. Access removal is confined to that route; a full passage ceiling replacement is not shown.

Electrical Scope

Two wet socket positions serve the diagnostic counter. The electrician isolated those outlets and marked their boxes for replacement. The dry passage lighting route remains in position; temporary protection is shown where ceiling access crosses it.

Microbial Observations

The small chase opening and removed wet skirting show no visible fungal material. The cavity above the sealed passage door was not part of the accessible area.

Mitigation Necessity

The drying contractor's site record places extraction and air movement along diagnostic room and staff passage. Wet cores and released adhesives were still visible at the survey openings. The crew logged equipment placement, follow-up moisture readings and removal of the drying equipment. Temporary barriers kept the wet work route clear of the retained occupied areas.

Service Chase Access Study

Access Requirement

Wet gypsum and loose floor finishes are marked D on the sketch. The dry passage ceiling and return panel are marked A, identifying the physical route needed to reach the connection. Access removal is confined to that route; a full passage ceiling replacement is not shown.

Camera-hole dimensions were smaller than the tool clearance required at the concealed connection. The passage strip and return panel obstruct that clearance.

Room Observation Register

Comparative meter readings are unitless indices on a 0-100 scale, not moisture percentages. Each room spot is compared with an adjacent retained substrate on the same instrument setting. Readings describe the visit condition and do not date the wetting.

Point / location	Assembly / record	Observation / method	Boundary / reference
1A - Diagnostic room	Wall bases	wet core at chase return	Ceiling above counter retained
1B - Diagnostic room	Inspection method	Visual survey of exposed surfaces and access opening	Field visit 2026-08-21; sample point 1
1C - Diagnostic room	Lower substrate spot reading	80 on relative 0-100 scale	Accessible surface beside wall bases
1D - Diagnostic room	Retained comparison point	13 on same instrument scale	Ceiling above counter retained
2A - Staff passage	Painted ceiling strip	dry finish at camera opening	Opening path marked A
2B - Staff passage	Inspection method	Visual survey of exposed surfaces and access opening	Field visit 2026-08-21; sample point 2
2C - Staff passage	Lower substrate spot reading	10 on relative 0-100 scale	Accessible surface beside painted ceiling strip
2D - Staff passage	Retained comparison point	9 on same instrument scale	Opening path marked A
3A - Chase return	Fixed millwork panel	sound but blocks tool access	Detach and reinstate
3B - Chase return	Inspection method	Visual survey of exposed surfaces and access opening	Field visit 2026-08-21; sample point 3
3C - Chase return	Lower substrate spot reading	11 on relative 0-100 scale	Accessible surface beside fixed millwork panel
3D - Chase return	Retained comparison point	11 on same instrument scale	Detach and reinstate

Schedule continued

Point / location	Assembly / record	Observation / method	Boundary / reference
4A - Counter recess	Socket boxes and plinth	water deposits and swelling	Two boxes isolated
4B - Counter recess	Inspection method	Electrical inspection after isolation	Field visit 2026-08-21; sample point 4
4C - Counter recess	Lower substrate spot reading	81 on relative 0-100 scale	Accessible surface beside socket boxes and plinth
4D - Counter recess	Retained comparison point	13 on same instrument scale	Two boxes isolated

Inspection Record

Working notes were entered during the 2026-08-21 visit. Room labels in the table follow the site route used by Naomi Brooks; they are not contractor estimate line numbers.

The table records inspected positions and comparison areas. It is not a full quantity takeoff or an invoice. Closed assemblies are distinguished from opened observations in the narrative.