Imaging Suite Repair Geometry

Visit Details

Claim: CLM-26-385027. Property: Northbend Imaging Center LLC, 1556 Alder Court, Suite E.

Inspection completed 2026-08-26 by Naomi Brooks.

The imaging suite has a continuous finish assembly across a procedure room and its control passage. Damage is concentrated around the equipment-service route, but the finish module crosses that boundary. Two contractors inspected the same marked area using different construction sequences.

Interior Scope

The marked wet footprint runs from the wash station across the passage and into the procedure-room entrance. Targeted removal can follow individual finish modules, leaving more joints to reinstate. Removing the larger continuous assembly reduces reinstatement joints but takes additional sound finish out with the wet area. Both sketches return the same usable room geometry.

Electrical Scope

The control-passage outlet route can be isolated independently of the imaging equipment feed. Wet low-level devices fall within both contractors' work boundaries. The retained equipment feed sits above the observed water path and passed the engineer's inspection.

Demolition Scope

Sketch T marks selective openings at the wet modules and individual access points. Sketch A marks removal of the connected finish assembly to the room boundaries. The sketches overlap at the same loss footprint; they are not north-room and south-room additions. Equipment protection is shown before either removal sequence.

Millwork Scope

The wash-station base and the continuous wall trim cross the finish module joints. The selective sequence detaches shorter sections for reinstatement. The assembly sequence lifts the continuous run while retaining the solid counter. Neither sketch includes new storage capacity or a room extension.

Prior Conditions

Openings beyond the wet modules show dry backing and secure fixings. The facilities drawing records the continuous assembly as installed before this event. No separate earlier repair patch was found at the proposed joint positions.

Microbial Observations

No visible growth was recorded at the selective test openings. The wider assembly remained closed during this inspection, apart from the comparison opening at its dry end.

Repair Methods

Sketch T marks selective openings at the wet modules and individual access points. Sketch A marks removal of the connected finish assembly to the room boundaries. The sketches overlap at the same loss footprint; they are not north-room and south-room additions. Equipment protection is shown before either removal sequence.

The selective sequence allows access through the passage after each shift but needs more small finish return visits. The assembly sequence closes the room for a continuous block and uses fewer reinstatement joints. The operator has not entered a construction sequence in the shutdown calendar.

Imaging Suite Repair Geometry

Room Observation Register

Comparative meter readings are unitless indices on a 0-100 scale, not moisture percentages. Each room spot is compared with an adjacent retained substrate on the same instrument setting. Readings describe the visit condition and do not date the wetting.

Point / location	Assembly / record	Observation / method	Boundary / reference
1A - Wash station	Wet finish modules	soft backing and raised edge	Both sketches include this area
1B - Wash station	Inspection method	Visual survey of exposed surfaces and access opening	Field visit 2026-08-26; sample point 1
1C - Wash station	Lower substrate spot reading	83 on relative 0-100 scale	Accessible surface beside wet finish modules
1D - Wash station	Retained comparison point	12 on same instrument scale	Both sketches include this area
2A - Control passage	Outlet route and ceiling	wet devices below dry equipment feed	Independent isolation available
2B - Control passage	Inspection method	Electrical inspection after isolation	Field visit 2026-08-26; sample point 2
2C - Control passage	Lower substrate spot reading	62 on relative 0-100 scale	Accessible surface beside outlet route and ceiling
2D - Control passage	Retained comparison point	14 on same instrument scale	Independent isolation available
3A - Procedure entrance	Continuous trim and floor joint	wet modules meet sound modules	Different joint treatment on sketches
3B - Procedure entrance	Inspection method	Lifted-edge adhesion comparison	Field visit 2026-08-26; sample point 3
3C - Procedure entrance	Lower substrate spot reading	73 on relative 0-100 scale	Accessible surface beside continuous trim and floor joint
3D - Procedure entrance	Retained comparison point	10 on same instrument scale	Different joint treatment on sketches
4A - Dry assembly end	Comparison opening	dry backing and secure fixings	Room geometry unchanged
4B - Dry assembly end	Inspection method	Visual survey of exposed surfaces and access opening	Field visit 2026-08-26; sample point 4

Imaging Suite Repair Geometry

Schedule continued

Point / location	Assembly / record	Observation / method	Boundary / reference
4C - Dry assembly end	Lower substrate spot reading	12 on relative 0-100 scale	Accessible surface beside comparison opening
4D - Dry assembly end	Retained comparison point	12 on same instrument scale	Room geometry unchanged

Inspection Record

Working notes were entered during the 2026-08-26 visit. Room labels in the table follow the site route used by Naomi Brooks; they are not contractor estimate line numbers.

The table records inspected positions and comparison areas. It is not a full quantity takeoff or an invoice. Closed assemblies are distinguished from opened observations in the narrative.