Procedure Room Work Sequences

Targeted Sequence

Sketch T: isolate the control-passage wet branch; lift individual wet modules; retain sound modules; reinstate additional local joints. The room geometry and existing storage remain.

Assembly Sequence

Sketch A: protect equipment; remove the connected finish assembly to its boundaries; reinstate the continuous run with fewer joints. The room geometry and existing storage remain.

Access Calendar

The targeted sequence allows passage access between shifts. The assembly sequence requires an uninterrupted room closure. The operating calendar supplied with these sketches has no selected construction period.